

BRUHATH BENGALURU MAHANAGARA PALIKE
Yelahanka Division, Yelahanka Zone

Executive Engineer
Yelahanka Division
B.B.M.P. Bengaluru - 64

No:EE/YNK-D/E-PMT/12/2022-23 Dated: 26-08-2022

APPROVED TENDER SCHEDULE -'B'

Item 78

Name of Work:-Repair and renovation to Samudaya Building at JP colony in ward no:05 Yelahanka New Town
Sub Division

Sl	Description	Unit	Approved Qty	Rate quoted by the contractor approved rates Sri AKHILESH C	
				Rate	Rate in Words
1	Demolishing R.C.C. work manually/ by mechanical means including stacking of steel bars and disposal of unserviceable material to the appropriate disposal area as per direction of Engineer-in-charge.	Cum	14.11	1798.54	One Thousand Seven Hundred NinetyEight Paise FiftyFour Only
2	Extra for cutting reinforcement bars manually/ by mechanical means in R.C.C. or R.B. work (Payment shall be made on the cross sectional area of R.C.C. or R.B. work) as per direction of Engineer-in-charge.	Cum	14.11	540.14	Five Hundred Fourty Paise Fourteen Only
3	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material to the appropriate disposal area as per direction of Engineer-in-charge.	Cum	12.72	357.19	Three Hundred FiftySeven Paise Nineteen Only
4	Dismantling tile work in floors and roofs laid in cement mortar including stacking material to the appropriate disposal area as per direction of Engineer-in-charge. For thickness of tiles above 25 mm and up to 40 mm.	Sqm	52.21	54.21	FiftyFour Paise TwentyOne Only
5	Providing and laying 52 mm thick cement concrete flooring with concrete hardener topping, under layer 40 mm thick cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) and top layer 12 mm thick cement hardener consisting of mix 1:2 (1 cement hardener mix : 2 graded stone aggregate 6 mm nominal size) by volume, hardening compound mixed @ 2 litre per 50 kg of cement or as per direction of Engineer incharge.	Sqm	47.97	682.44	Six Hundred EightyTwo Paise FourtyFour Only
6	Providing and laying Vitrified tiles in different sizes (thickness to be specified by manufacturer), with water absorption less than 0.08 % and conforming to I.S. 15622, of approved make, in all colours & shade, over 12 mm thick bed of cement mortar 1:3 (1 cement: 3 coarse sand), jointing with grey cement slurry @ 3.3 kg/ m2 including grouting the joint with white cement & matching pigments etc. complete	Sqm	47.97	105.34	One Hundred Five Paise ThirtyFour Only
7	Providing and Fixing pre cast covering Slab made out of CC 1:2:4 with 10cm thick and Finishing cutting ,including form work,curing,including cost of all materials, labour,hire charges of machinery,loading,unloading,lead and lift,transportation etc ,complete.	Sqm	99.00	1823.36	One Thousand Eight Hundred TwentyThree Paise ThirtySix Only

Akhilesh C

[Signature]
Executive Engineer
Yelahanka Division
Yelahanka Zone
B.B.M.P. Bengaluru - 64
560064

	Earth work excavation by manual means for drains, canals, waste weir, draft, approach channels, key trenches, foundation of bridges and such similar works in all kinds of soils, as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter, excavated surface leveled and sides neatly dressed disposing off the excavated stuff or sorting & stacking the selected stuff for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools & other appurtenances required to complete the work. Depth exceeding 1.5m, but not exceeding 3 m	Cum	3.00	192.63	One Hundred NinetyTwo Paise SixtyThree Only
9	Providing and Filling in foundation with granite / trap broken metal 100mm. and down size, with approved sand including hand packing, ramming, watering, including cost of all materials and labour with all lead and lift. complete as per specifications.	Cum	0.20	2479.05	Two Thousand Four Hundred SeventyNine Paise Five Only
10	Providing and laying in position plain cement concrete for levelling course for all works in foundation. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machineries, curing, and all the other appurtenances required to complete the work as per technical specifications. Mix 1:3:6 (M10) Using 40 mm nominal size graded crushed coarse aggregates.	Cum	0.30	5376.27	Five Thousand Three Hundred SeventySix Paise TwentySeven Only
11	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations and other similar works etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m.	Cum	1.90	197.47	One Hundred NinetySeven Paise FourtySeven Only
12	Providing and laying in position Reinforced cement concrete for all Sub structures of building, Irrigation works, Sub structure works of bridges, Drain works & other parallel works from 0.50m to 3.50 m height. The granite/ trap/ basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers, laid in layers, well compacted using needle vibrators, providing weep holes wherever necessary, including all lead & lifts, cost of all materials of quality, confirming to the requirements of relevant IS codes, labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork to be paid separately) M25 Design Mix Using 20 mm nominal size graded crushed coarse aggregates	Cum	0.60	6380.28	Six Thousand Three Hundred Eighty Paise TwentyEight Only

Akhilsh. c


Executive Engineer
 Yelahanka Division
 Yelahanka Zone
 Bruhat Bangalore Mahanagara Palike
 BANGALORE - 560 075

	Providing and laying in position Reinforced cement concrete for all Super structures of building , Road works, Water works, Irrigation works & super structure works of bridges upto 3.50 m height. The granite/ trap/ basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers laid in layers, well compacted using needle vibrators. The cost includes all lead & lifts, cost of all materials, quality confirming to the requirements of relevant IS codes , labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement, dowel bars & formwork to be paid separately) M25 Design Mix Using 20 mm nominal size graded crushed coarse aggregates-Columns upto top slab	Cum	1.44	6586.85	Six Thousand Five Hundred EightySix Paise EightyFive Only
14	Beams	Cum	0.23	7185.66	Seven Thousand One Hundred EightyFive Paise SixtySix Only
15	Staircase	Cum	2.11	7185.66	Seven Thousand One Hundred EightyFive Paise SixtySix Only
16	Providing Thermo-Mechanically Treated bars of grade Fe-550 Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position, binding and anchoring to adjacent members wherever necessary complete as per Design including cost of material, labour, usage charges complete as per specifications. (The laps and wastages shall not be measured separately)	Tonne	295.00	92.93	NinetyTwo Paise NinetyThree Only
17	Providing and constructing load bearing wall with Solid Concrete blocks of size 400x150x200mm having block density more than 1800kg/m ³ and minimum compressive strength of 4.00 N/mm ² conforming to IS 2185 (Part - I) - 2005 and constructed with CM 1:4 as per IS 2572:2005 including cost of all materials, labour, scaffolding and curing, usage charges of machinery etc complete as per specifications.	Sqm	23.92	1027.05	One Thousand TwentySeven Paise Five Only
18	Dismantling plastering and removing the debris with a lead upto 200m.	Sqm	138.35	35.82	ThirtyFive Paise EightyTwo Only
19	Providing 18 mm cement plaster in two coats under layer 12 mm thick cement plaster with cement mortar 1:5 (1 cement : 5 coarse sand) and a top layer 6 mm thick cement plaster with cement mortar 1:3 (1 cement: 3 coarse sand) finished rough with sponge to brick masonry including rounding off corners wherever required smooth rendering, providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications and as per directions of Engineer-in-charge.	Sqm	108.77	311.70	Three Hundred Eleven Paise Seventy Only
20	Providing 20 mm cement plaster of mix :1:4 (1 cement: 4 fine sand) to brick/stone masonry including rounding off corners wherever required smooth rendering, providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications and as per directions of Engineer-in-charge	Sqm	23.92	289.43	Two Hundred EightyNine Paise FortyThree Only
21	Providing 12mm thick cement plaster in floating coat of neat cement of mix :1:4 to Brick masonry including rounding off corners wherever required smooth rendering, providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications and as per direction of Engineer-in-charge	Sqm	46.33	253.62	Two Hundred FiftyThree Paise SixtyTwo Only

Abhilash

	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete as per specifications and as per directions of Engineer in charge.	Sqm	134.40	80.34	Eighty Paise ThirtyFour Only
23	Finishing walls with Acrylic Smooth exterior paint of required shade :New work (Two coat applied @ 1.67 ltr/10 m ² over and including priming coat of exterior primer applied @ 2.20 kg/10 m ²) with paint of approved quality to give an even shade, after thoroughly brooming the surface to remove all dirt, dust, mortar drops and foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour complete as per specifications and as per directions of Engineer-in-charge	Sqm	205.02	131.65	One Hundred ThirtyOne Paise SixtyFive Only
24	Finishing with Epoxy paint (two coats) at all locations prepared and applied as per manufacturer's specifications including appropriate priming coat, preparation of surface, etc. complete. On concrete work including preparing the surface after thoroughly cleaning oil, grease, dirt and foreign matter, cost of materials, labour complete as per specifications and as per directions of Engineer-in-charge.	Sqm	261.02	133.58	One Hundred ThirtyThree Paise FiftyEight Only
25	Providing and laying 52 mm thick cement concrete flooring with concrete hardener topping, under layer 40 mm thick cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) and top layer 12 mm thick cement hardener consisting of mix 1:2 (1 cement hardener mix : 2 graded stone aggregate 6 mm nominal size) by volume, hardening compound mixed @ 2 litre per 50 kg of cement or as per direction of Engineer incharge.	Sqm	8.33	716.76	Seven Hundred Sixteen Paise SeventySix Only
26	Providing and placing on terrace(at all floor levels), polyethylene water storage tanks as per IS 12701 marked,with cover and suitable locking arrangement and making necessary holes for inlet,outlet and overflow pipes but without fittings and the base support for tank(For 1000 litre capacity)	Ltr	3000.00	7.92	Seven Paise NinetyTwo Only
27	Providing and laying water proofing treatment to the Roof with PU based single component elastomeric pure polyurethane based coating on New terrace/Chajjas/Sunken portion of WC:Bathroom, cold applied PU waterproofing membrane that is highly elastic with elongation greater than 400% and tensile strength greater than 2MPa as per ASTM D412. The waterproofing membrane to be applied in 2coats @ 1.6kg per m ² to achieve final DFT (dry film thickness) of 1mm including prime coat of epoxy primer @150 g per m ² and protection with 120gsm Geo-textile over the waterproofing membrane. The finished cost to include surface preparation, making coving at Junction, Bore Packing, treatment of construction joints completely as per specification & with a 10 years warranty on product & work from certified manufacturers as per the direction of the Engineer In charge	Sqm	73.64	737.55	Seven Hundred ThirtySeven Paise FiftyFive Only
28	Providing and fixing white vitreous china pedestal type water closet (European type) with seat and lid, 10 litre low level white vitreous china flushing cistern & C.P. flush bend with fittings & C.I. brackets, 40 mm flush bend, overflow arrangement with specials of standard make and mosquito proof coupling of approved municipal design complete, including painting of fittings and brackets, cutting and making good the walls and floors wherever required :W.C. pan with ISI marked white solid plastic seat and lid	Each	2.00	4954.95	Four Thousand Nine Hundred FiftyFour Paise NinetyFive Only

APRIL 2018

	Providing and fixing one piece construction white vitreous china squatting plate with an integral longitudinal flushing pipe, white P.V.C. automatic flushing cistern, with fittings, standard size G.I. / PVC flush pipe for back and front flush with standard spreader pipes with fittings, G.I clamps and C.P. brass coupling complete, including painting of fittings and cutting and making good the walls and floors etc. wherever required : Single squatting plate with 5 litre P.V.C. automatic flushing cistern	Each	2.00	5147.01	Five Thousand One Hundred FourtySeven Paise One Only
30	LED Indoor Supplying of 2' feet - LED PVC Square Batten ..W with high quality diffuser with Life of 25000 burning hours & 70% lumen maintenance with CRI > 80. Power Input: 220-240V @ 50Hz & Power factor >0.9 along with CE approved drivers. 5 years Warranty against any manufacturing defect working under standard electrical condition LED light fighting 4' - 28 watts complete and as per the directions of the Engineer-in-charge of the work	Each	15.00	446.40	Four Hundred FourtySix Paise Fourty Only
31	Supplying and fixing of slim patty fitting, made out of CRCA Sheet metal body with locking type holder completely wired Excluding Ballast & Fluorescent Tube	Each	8.00	1876.50	One Thousand Eight Hundred SeventySix Paise Fifty Only
32	Supplying heavy gauge PVC conduit pipe mm dia.....mm thick confirming to IS 2509 with suitable size bends, metal/PVC Junction boxes, adhesive paste etc., and running before concreting the slab. The conduit should be tied to the reinforcement rods by using binding wires and unused ways of junction boxes and pipe ends should be covered using PVC end enclosures, run with 18SWG GI fish wire wherever necessary 25mm dia 2mm thick(including audio system)complete and as per the directions of the Engineer-in-charge of the work 25mm dia 2mm thick	M	40.00	63.00	SixtyThree Only
33	Supply and delivery of Centrifugal pumpset at site brand new best make and with discharge duty confirming to ISI standards and its latest amendments 2 HP, Size 50x40 Head 22M, Discharge 186 LPM	Each	2.00	17295.30	Seventeen Thousand Two Hundred NinetyFive Paise
34	Supplying of Ceiling Fan with Capacitor rating As per guideline of BEE 5 star rating and IS:374/79 and also comply with IS: 1709/1984 with latest amendment, Rated voltage 220 V/50 Hz, Rated power input 48 W +/- 10 %, Rated current As per IS:374/79, Rated power factor 0.9 lagging(min), Rated speed 350 +/- 10% RPM, Rated air delivery 210 +/- 10% Cubic Meter Minimum, Rated service value 4.2 CMM / W, Three Blades of blade leaf 1.05 mm thick Aluminium Alloy sheet, Class B motor insulation, Bearing Two ball bearings, Top 6202, Bottom 6201, as per IS specification, Motor winding. Temp rise Shall not exceed 75 deg C over and ambient of 40 0C by resistance method at 245 V, Insulation resistance Shall not be less than Two Mega Ohms (2M Ohms), Leakage current Should not exceed 210 Micro Amp, Power input, W& current, Air Delivery & Fan Speed as per IS:374/1979 with latest amendment, 2 year manufacturer Warranty.	Each	4.00	2654.10	Two Thousand Six Hundred FiftyFour Paise Ten Only
35	Round S S Chairs for samudhayabhavana. complete as per specification and Directions of Engineer In Charge.	Nos	40.00	1170.00	One Thousand One Hundred Seventy Only
36	Spacepanda Apollon Full Stainless Steel Folding Table, 18 gauge ,multipurpose table, Metal conference table (Free Standing , finish color - Grey, pre- assembled) for samudhayabhavana. complete as per specification and Directions of Engineer In Charge.	No	7.00	15210.00	Fifteen Thousand Two Hundred Ten Only

Akhilush. c

	GREEN SOUL Seoul-X Mid Back Ergonomic Chair (Home Office, WFH Moulded Foam Extra Comfort Faabric Office Executive Chair complete as per specification and Directions of Engineer In Charge.	Each	1.00	5901.48	Five Thousand Nine Hundred One Paise FourtyEight Only
38	Godrej Boltless Rack for Storing books of all types. complete as per specification and Directions of Engineer In Charge.	Each	1.00	19773.00	Nineteen Thousand Seven Hundred SeventyThree Only
39	Nilkamal Metalica visitor Chair, complete as per specification and Directions of Engineer In Charge.	Each	3.00	2808.00	Two Thousand Eight Hundred Eight Only
40	Four Shelf Almirah for Office and institutional usage .made with painted or powder coated ISI Grade mild steel body complete as per specification and Directions of Engineer In Charge.	Each	1.00	14625.00	Fourteen Thousand Six Hundred TwentyFive Only
41	Woodyou Acura Office Table - home office desk designed to effortlessly hide computer equipment complete as per specification and Directions of Engineer In Charge.	Each	1.00	8656.83	Eight Thousand Six Hundred FiftySix Paise EightyThree Only
42	Rubber door mats. complete as per specification and Directions of Engineer In Charge.	Each	6.00	292.50	Two Hundred NinetyTwo Paise Fifty Only


Signature of the
Contractor


Executive Engineer,
Yelahanka Division,